

SHIMOGA DIVISION.

Dated 30th March 1912.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 28th April 1912, for constructing quarters for 8 Barr Sepoys at Tirthahalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for 8 Barr Sepoys at Tirthahalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the.....Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
1.	Earthwork excavation	C. yd.	128
2.	Burnt stone in chunam foundation and basement	C. ft.	5,085
3.	Burnt brick in chunam superstructure	"	5,766
4.	Burnt stone slabs, dressed and fitted	S. ft.	476
5.	Chunam plastering	Sq.	123.20
6.	White and colourwashing	"	123.20
7.	Coping with burnt brick in chunam and chunam plastering.	R. ft.	293
8.	Chunam borders	"	64
9.	Teakwood work wrought and put up with oiling	C. ft.	215
10.	Roofing with 1st class Mangalore patent tiles, teak reepers, etc., complete.	Sq.	33.40
11.	Mangalore patent ridge tiles set in mortar and cement pointing.	R. ft.	93
12.	Teakwood battened doors, complete	S. ft.	408
13.	Teakwood battened windows with iron bars	"	70
14.	Teakwood ventilators do	"	48
15.	Chocolate painting	Sq.	10.52
16.	Teakwood pegs	Each	32
17.	Flooring with Cuddapah slabs	Sq.	14.36
18.	Filling with gravel, watering and tamping	C. yd.	47
19.	Clearing site and levelling ground	Lump sum.	Rs.
20.	Shaped drain, complete	R. ft.	250
21.	Painting with cement and chunam mixed	Sq.	33.40
22.	Compensation for land to be acquired	Lump sum.	Rs.

F. A. STEELE,
Executive Engineer.